SHIMOGA DIVISION.

Notification dated 12th January 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 10th February 1939, for constructing a Town Hall at Sorab, Simoga District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury Challan for Rupees three hundred and twenty-five for having credited the earnest money, to "17 (*a*) P. W. Deposits" and be superscribed "Tender for constructing a Town Hall at Sorab, Shimoga District" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Tenders must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. The successful tenderer will have to deposit another sum of Rs. 325 towards the security deposit before the execution of contract agreement.

14. Cement will be supplied by the department and only labour charges should be quoted for such of the items.

Abstract estimate for constructing a Town Hall at Sorab, Shimoga District.

No.	Items of work	Unit	Rate	Quantity	Rate in	
					Words	Figures
			Rs. a. p.			
1	Clearing site and levelling premises including cutting jungle and trees	L. S.	..	..		
2	Dismantling old structure	C.ft.	0 0 6	3,610		
3	Do to be done steps near platform and front steps	,,	0 0 6	199		
4	Excavating foundations behind old basement	C.yd.	0 4 0	25		
5	Removing earth from inside structure and spreading same	,,	0 3 0	103		
6	Earthwork filling in verandah	,,	0 3 0	72		
7	Lime concrete for foundation Main Building	C.ft.	0 5 9	796		
8	Masonry in clay with available old laterite bricks in foundation	,,	0 2 6	947		
9	Masonry with available old laterite bricks in lime mortar in basement	,,	0 3 6	1,100		
10	Masonry of brick in mud superstructure ..	,,	0 4 0	1,606		
11	Do of new laterite bricks in mortar plat form and steps	,,	0 6 6	272		

No.	Items of work	Unit	Rate	Quantity	Rate in	
					Words	Figures
			Rs. a. p.			
12	Plastering with lime mortar	Sqr.	5 0 0	30·20		
13	Pointing basement with lime mortar ..	,,	5 0 0	2·12		
14	Plastering with cement mortar ½" thick ..	,,	10 8 0	0·35		
15	Flooring with cement ¼ thick and jelly concrete 3" thick	C.ft.	0 5 9	128		
16	Flooring cement plastering ½" thick including cutting squares	Sqr.	10 8 0	5·84		
17	Teakwood doors battened with shutters and fittings, complete	S.ft.	1 8 0	288		
18	Teakwood windows battened with iron bars and fittings, etc., complete	,,	1 12 0	168		
19	Trellis work to ventilators	,,	2 0 0	73		
20	R.C. slabs 4" to 5" thick for lintels of doors	,,	0 14 0	217		
21	Cement concrete slabs (1 : 2 : 4) 4" to 5" thick for coping over verandah wall ..	,,	0 7 0	204		
22	Teakwood wrought and put up with wood oiling 2 coats	C.ft.	5 0 0	60·66		
23	King post trusses	,,	6 0 0	10		
24	Silicate painting 2 coats	Sqr.	5 4 0	9·12		
24-A	Roofing with 1st class Mangalore tiles on teak reepers, etc., complete ..	,,	32 0 0	7·08		
25	Terracing near rooms	,,	75 0 0	1·92		
26	Parapet do	R.ft.	1 8 0	38		
27	Cornice as per design	,,	1 0 0	38		
28	Sun shades over doors and windows ..	L. S.	..			
29	R.C. bearing slab 3" thick 86' long 2' wide with 6" projection at 1 per R.ft. less provision of Rs. 52 made in original estimate for wall plate	,,	..			
30	Ridge tiles set in mortar	R.ft.	1 0 0	24		
31	Finials	Each	1 0 0	2		
32	Eave board around tiled roof	R.ft.	0 8 0	98		
33	Tarring ends of rafters sides of door frames, etc.	L. S.	..			
34	Colour washing and white washing as per lime plastering	Sqr.	0 5 0	30·20		
35	Partition wall of junglewood planks 1" thick between rooms with 2 coats of wood oiling	S.ft.	0 12 0	64		
36	Carting sand from River and spreading ..	Each cart	1 8 0	12		
37	Junglewood post 10' long and 7" dia. with bracket pulley, clamps, etc., including whitelead painting post	Each	8 0 0	1		
38	Laying out a circle with lamppost in the centre—					
	(*a*) Curbing with curb stones including dressing	S.ft.	1 0 0	94		
	(*b*) Guard stones 1½' long 7" dia. ..	Each	2 0 0	8		
	(*c*) Casuarina post 14' long and 8" dia. with bracket, pulley, etc., including whitelead painting	,,	5 0 0	1		
	(*d*) New laterite brick masonry in mud for pedestal of lamp post	C.ft.	0 4 6	27		
	(*e*) Lime mortar plastering with cement wash to the above masonry	Sqr.	5 8 0	8·29		
	Verandah.					
1	Reinforced concrete pillars (with 1 per cent reinforcement) with base and capital and brackets as per design (all cast together)	Each	18 0 0	26		
	Preparing and fixing R.C. beams 136 × ½ × ¾— 51 c.ft.	C.ft.	2 8 0	51		
3	R.C. ventilator sun-shade slabs 2" thick as per design	S.ft.	1 0 0	290		

No.	Items of work	Unit	Rate	Quantity	Rate in	
					Words	Figures
			Rs. a. p.			
4	R.C. cornice precast as per design	R.ft.	1 0 0	141		
5	Brick in lime mortar parapet 9" thick 2' high as per drawing	,,	1 8 0	141		
6	Reinforced cement concrete (1 : 2 : 4) terrace with 4" thick slab reinforced with ½" Q to Q, 6" C to C and ¼" Q @ 12" C to C distribution bars plus 3" to 6" of surki concrete two courses of flat tiles and smooth plastering on top with proper sloping at 1 in 30 to rain off rain water including ceiling plaster complete	Sqr.	75 0 0	9.18		
7	Rain water pipes, etc.	L.S.				

M. K. RAJAM IYENGAR,
Executive Engineer.

KADUR DIVISION.

Notification dated 15th January 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, Chikmagalur, upto 3 P.M. on 6th February 1939, for constructing an additional block to the Government Middle School at Birur.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kadur Division, should be addressed to the Executive Engineer, Kadur Division, Chikmagalur, in a sealed cover and superscribed as "Tender for constructing an additional block to the Government Middle School at Birur." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a Treasury chellan for Rs. 150 (Rupees one hundred and Fifty only) for having credited this earnest money to "17-A-P.W.D. Deposits." The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest. Tenders unaccompanied by earnest money will not be accepted.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 6th February 1939 at Chikmagalur. The final acceptance of the tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the Departmental Schedule Contract Form, for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Chikmagalur, on all working days, between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.